



# Cricket Irrigation Contract Specification

## Title

Cricket Irrigation at The Park

## Reference

Cricket Irrigation

## Location

The Park, School Road, Frampton Cotterell, Bristol, BS36 2DA.

## Deadline

Quotes to be received by 9th April 2021 (12:00 midday).

## Start Date

The start date is flexible, to start as soon as possible. Your approximate available start date should be stated within your quotation.

## Department responsible

Projects, Frampton Cotterell Office.

## Description

To install an irrigation system to supply x2 cricket squares with water, connecting a water tank to existing underground pipes (if applicable\*) and existing hydrant boxes. The outfield is not watered. The largest square is 20.5m x 37m, thus water requirements must meet this size for use with the clubs' plug in sprinklers. Domestic sled and tripod garden sprinklers are currently used by the clubs, but larger capacity sprinklers may be used in future. One tank of appropriate size is to be installed to supply both squares on the same site. Smaller tank options preferred if applicable, but the most suitable tank size is to be decided by the contractor. All works to be WRAS compliant and fit within local water regulation guidelines.

## Quote specification

The works will include:

1. \*To undertake a survey of the existing pipe work connecting to the cricket pitch in Area 1 (appendix 1 & 2) to ensure the pipe is fit for purpose and has minimal leakage present.
2. Installation of a water tank with pump system and type AA/AB air gap, size of tank to be suitable for the requirements to water two cricket squares (note: it is usual practice that only one pitch is watered at once).
3. Frost protection of tank if required.

4. Groundworks to redirect and connect existing underground pipes from both pitches to the water tank.
5. Connection of the water tank to the mains water connection and all associated plumbing works (mains water on site connecting to sport building).
6. To install a concrete base for the tank if required.
7. Electrical wiring of unit.
8. DCVA to be fitted on the branch to the storage tank due to seasonal use.
9. The new and existing installation shall be flushed disinfected and pressure tested.
10. All works to comply with the Water Supply (Water Fittings) Regulations 1999.
11. Water fittings to meet the requirements of regulation 4 (1)(a) and be suitable for the circumstance in which they are used.
12. If the works are going to be awarded to a member of WaterSafe the works shall be certificated as compliant with the WS(WF)R 1999.

## General prescriptions

- a) Payments to be made on receipt of an invoice to Frampton Cotterell Parish Council.
- b) The contractor must indemnify the Council against any liability in respect of any damage caused to any land, building, property or person arising from or connected to the performance of this contract.
- c) The contractor must ensure that all operatives working on this contract comply with relevant Health & Safety legislation and provide the Council with the company's up-to-date Health & Safety Policy.
- d) The contractor must hold relevant insurances and supply a copy of liability to the Council.
- e) Contractors may be required to carry out additional works on instruction of the Clerk. Such works should be invoiced as additional costs.

## Contact

Contact Daisy Finniear with any questions and to submit a quote:

Email: [projectofficer@framptoncotterell-pc.gov.uk](mailto:projectofficer@framptoncotterell-pc.gov.uk)